

DESIGN OF A FORCE-CONTROLLED CARTILAGE BIOREACTOR FC Bioreactor: Jeffery Guo¹, Emilio Lim², Griffin Radtke¹, Sydney Therien² Advised By: Dr. Corinne Henak^{1,2} (Client) and Dr. Paul Campagnola² Departments of Mechanical Engineering¹ and Biomedical Engineering², University of Wisconsin-Madison



Final Design & Supporting Criteria

Overall, the bioreactor consists of three components: housing, actuation, and the supporting circuitry.



Figure 3. Schematic overview of the final bioreactor design

Incubator-Safe

Fits within 20 x 21 x 25 [in³] incubator

Can operate within 37 °C, humid environment

Aseptic technique friendly

Physiological Force Output

Capable of inducing 20% ε_{engr} on cartilage samples

Applied displacement must be force-controlled

Cyclic loading profile (0.1 – 10 [Hz])

Figure 4. Specifications used to inform and guide design

Circuitry Design & Testing

Comparison of Potential Circuit Designs

Criterion	PCB	H-Bridge	Transistor
Functionality (15)	1 (3)	5 (15)	5 (15)
Ease of Use (10)	2 (4)	3 (6)	4 (8)
Space (10)	2 (4)	3 (6)	5 (10)
Price (5)	5 (5)	1 (1)	1 (1)
Total (40)	16	30	34



Figure 5. Setup to control VCA with triangle voltage generator



Figure 6. Setup to contro VCA with H-bridge circuit and Arduino



Figure 7. Setup to control VCA with transistor circuit

Wall Panels Acrylic

Compressive Interface PTFE

Sample Tray PLA

Alignment drylin Q flange bearing

Actuation Thorlabs Voice Coil Actuators (VC-125C)

Base Module PLA

Budget-Friendly

In total, housing, actuators, and circuitry must cost ≤ **\$5000**

Final Circuit Design



Results & Discussion

Objectives

- Validate consistent force output over long durations of operation (15-30 mins)
- 2. Validate correct force output
- Determine any deviations from the desired force value and percent overshoot

Findings

- Force is relatively consistent, with minimal variation over time
- Successfully outputs 6 N of force
- There is overshoot occurring roughly every 15 s; needs to be quantified

Summary and Future Work

To analyze the relationship between mechanical loading over long timescales and cartilage osteoarthritic degradation, a bioreactor was designed and built.

Semester Accomplishments

Designed and built a 1D actuator and circuit system to specifications

Next Steps

References and Acknowledgements

[1] Hunter, D. J., March, L. & Chew, M. Osteoarthritis in 2020 and beyond: a Lancet Commission. The Lancet 396, 1711–1712 (2020) [2] Mohd Yunus, M. H., Lee, Y., Nordin, A., Chua, K. H. & Bt Hj Idrus, R. Remodeling Osteoarthritic Articular Cartilage under Hypoxic Conditions. International Journal of Molecular Sciences 23, 5356 (2022).

Funding from NSF-BMMB-2237707 is gratefully acknowledged





Built a housing prototype that can be used for experimentation

1. Test the unit in an experimental setting with full assembly 2. If testing goes well, order and print the components to scale up the bioreactor to include remaining samples 3. Machine the housing out of aluminum (hire TeamLab staff)

> See our project page for more info!